

A garden-facing part of the living space

Revised plan 1:100 at A3, printed at 100% | Original exterior footprint and room positions retained



THE CHANGE

Remove the internal sliding doors and wall to the shared room.
Open the wall to the shared hall.
Relocate its door beyond the snug.

The former orangery becomes an open, year-round garden sitting area beside the main living space.

THE CONNECTIONS

4.00 m open edge to shared living.
3.50 m open edge to shared hall.
These are wall-removal dimensions; beam bearings or posts may reduce the finished clear openings.

New 0.90 m door across the hall separates office and guest rooms.
Snug and WC stay on the shared side.

YEAR-ROUND DESIGN

Design heating, ventilation and summer shading together with the shared room. No internal separating doors enclose the garden sitting area.


Low garden-room roof retained as the current form. The ceiling meets the taller vault at a broad opening; its overhead detail is not resolved.

GIA unchanged: 319.91 m².
Footprint unchanged: 360.26 m².
All nine nominated routes checked.

Open the garden room, close off the guest wing


Before and after at 1:50 on A3 | View orientation matches the plan above

BEFORE / ENCLOSED ORANGERY



1.10 m sliding connection to the main shared room.
0.90 m hinged door to the guest hall.
Internal walls make this a separate room.

AFTER / OPEN GARDEN SITTING AREA



Brown dashed: former wall positions, removed in this study.
Green dashed: checked routes through the open corner.
Door beyond the snug separates office and guest rooms.

The hall door is beyond the snug when walking from shared living. It swings toward the office; the existing office door stays.
Full garden-room openings are the intent; beams, bearings and a possible corner post still require structural design.
The 14.00 m2 garden sitting zone includes former wall and doorway-threshold strips. Overall GIA does not increase.
Geometry checks cover room/furniture fit, retained doors and sampled 0.70 m routes; they do not establish structural or environmental performance.